



Newberry Township, PA

\$2.2M Construction Cost Includes Process, Headworks, Control Building & UV Disinfection



Plant Highlights

Project Location:
York Haven, PA

Client:
Newberry Township

Size:
Average Flow 1.3 MGD
Peak Flow 2.6 MGD

Representative:
Watermark Environmental
Systems

- SEQUOX Nutrient Removal
- Stainless Steel Clarifier has no moving parts below water
- Clarifier controls effluent flow rate while allowing continuous flow
- 125 hp blower supplies all aeration
- Sliderail Diffuser Access System provides simple access to aeration diffusers
- Anoxic Selector Tank helps control filamentous bacteria
- Common-wall construction for expansion
- Floating skimmers for scum removal

